मात्रा विवरण पत्रक

संकल्पा असोसियटस

आर्चिटेक अँड इनटिरियर डिज़ाइनर्स

1001, इलेवन हाइट्स, संत गोरा कुम्भार मार्ग, कुम्भरवाड़ा, धारावी, मुंबई – 400 017 मो.: 9869031498

बैंक ऑफ इंडिया की सीप्ज़ एमसीबी शाखा की छत पर शेड

अनु	विवरण				
क्र		मात्रा		दर	राशि
1	0.80 मिमी मोटाई वाली कॉरुगेटेड G.S. शीट रूफिंग, जिसमें जिंक कोटिंग कम				
	से कम 275 ग्राम प्रति वर्ग मीटर हो, रिड्ज या हिप्स सहित, क्षैतिजऊर्ध्वाधर या /				
	वक्र सतहों पर लगाई जाएगी। शीट को पोलिमर कोटेडJ या L हुक्स, 8 मिमी				
	व्यास के बोल्ट और नट्स के साथ बिटुमेन और गैल्वेनाइज्ड)G.I.) लिम्पेट वाशर				
	या सफेद सीसे से भरे G.I. लिम्पेट वाशर के माध्यम से सुरक्षित किया जाएगा।				
	आवश्यकतानुसार शीट को सही आकार और माप में काटा जाएगा। शीट्स की				
	ओवरलैपिंग पर अनुमोदित स्टील प्राइमर की एक परत और दो परतें पेंट लगाई				
	जाएंगी। इसमें संरचनात्मक स्टील कार्य शामिल होगा, जो रिवेटेड, बोल्टेड या				
	वेल्डेड बिल्टअप सेक्शन्स-, पर्लिन्स, रैफ्टर्स, ट्रसेस और फ्रेम्ड वर्क के रूप में होगा।				
	सभी काटने, उठाने, स्थिति में लगाने और अनुमोदित स्टील प्राइमर की एक		वर्ग		
	प्राइमिंग कोट लगाने का कार्य पूरा किया जाएगा।"	4000	फूट		
	जीएसटी 18%			रुपये	
	कूल				
				रुपये	

नोट: उपरोक्त मात्राएँ अनुमानित हैं और वे बढ़ या घट सकती हैं। ठेकेदार को प्रत्येक आइटम के अनुसार केवल वास्तविक रूप से किए गए कार्य के लिए भुगतान किया जाएगा। प्रत्येक आइटम के लिए संक्षिप्त विनिर्देश दिए गए हैं। डिज़ाइन और विनिर्देश में मामूली परिवर्तन संभव हैं, जिसके लिए कोई अतिरिक्त भुगतान नहीं दिया जाएगा। इनमें से कोई भी आइटम रद्द किया जा सकता है।

नोट: लागत में जीएसटी को छोड़कर सभी कर शामिल हैं। ठेकेदार के अनुमान में MMC / स्थानीय प्राधिकरणों से अनुमित भी शामिल होनी चाहिए ताकि कार्य सुचारू रूप से चल सके।

Note: In case of any discrepancy in English & its Hindi translation, for interpretation and legal aspects, the English version shall prevail.

BILL OF QUANTITIES

SANKALPA ASSOCIATES

Architects & Interior Designers

1001, Eleven Heights, Sant Gora Kumbhar Marg, Kumbharwada, Dharavi, Mumbai 400 017, Mobile: 9869031498

Shed at Terrace of SEEPZ MCB Branch of Bank of India

No	Description	Quantity		Rate	Amount
1	Providing & fixing corrugated 0.80 mm thick with zinc coating not less than 275 gm/m² G.S. sheet roofing including ridges or hips, vertical / curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead, including cutting to size and shape wherever required with a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (up to any pitch in horizontal/ vertical or curved surfaces), including Structural steel work riveted, bolted or welded in built up sections, purlins, rafters and trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	4000	Sq.ft.		
	GST 18%			Rs.	
	Total			Rs.	

NOTE: The above quantities are approximately taken for estimation purpose they may increase or decrease. Contractor will be paid for actual work executes against each item. Brief specifications are given for each item. Minor verification in design and specification for each item are likely for which no extra payment will be given. Any of these items may be cancelled.

NOTE: Cost inclusive of all taxes other than GST. The Contractor estimate shall also include MMC/ Local Authorities Permission for smooth functioning the work.