

BILL OF QUANTITY OF INTERIOR DESIGN AND FURNITURE WORKS FOR BANK OF INDIA , AT MIRGANJ BRANCH					
Sl. No.	DESCRIPTION	UNIT	QTY.	RATE	AMOUNT
1	Flooring Providing & laying of 2' x 2' Vitrified Tile flooring of approved make & shade viz. RAK (IMP-OFGY) or EURO (ATHENA) over necessary leveling screed of 1:4 cement mortar (20mm thick) with proper slope wherever required including pointing of the joints with white cement and matching pigments, curing etc. complete in all respects (excluding Toilets and Non – Customer area).	S.Ft.	0.00		
2	Facade of Entrance Door- Refer Dwg.no.11 Providing and fixing in position Aluminium composite panel Boxing with PVDF coating & LDPE core laminated Eurobond / Altobond/ Alukbond Exterior Grade 4 mm thick with composite of (0.5mm-3mm-0.5mm) including fabrication for the same with aluminium sections, required hardware, silicon sealant (Dow Corning 789) masking tape, necessary scaffolding etc. as detailed in drawing no.(11) complete in all respects.	S.Ft.	85.00		
3	False Ceiling (Armstrong) Providing & fixing in position false ceiling in Armstrong 600 x 600 mm x 15/16 mm Dune Supreme RH 99 Prima tile with Tegular edge framework as specified by Armstrong Co. with suspenders wherever required. Making necessary framework for A.C. ducting, if any, and necessary cutouts for diffusers and light fittings, taping and finishing to proper line & level, including making grooves and trap doors for A.C unit in 18mm thick M.R. Grade Plywood with Stainless Steel hinges & locks with moulding 1" x 1" for edges including finishing with White Plastic Emulsion Paint etc. complete in all respects. (Note:- Only the plan area will be measured for payment. No extra payment will be made for cutouts, grooves, mouldings etc.)	S.Ft.	916.00		
4	False Ceiling (Gypsum Board) Providing & fixing in position false ceiling in Gypboard 12mm thick for horizontals & verticals fixed over G.I. framework as specified by India Gypsum Co. Ltd. including trap doors for A.C unit. in 18mm thick M.R. Grade Plywood with Stainless Steel hinges & locks with moulding 1" x 1" for edges including finishing with White Plastic Emulsion Paint etc. complete in all respects. (Note:- Only the plan area will be measured for payment. No extra payment will be made for cutouts, grooves, mouldings etc.)	S.Ft.	590.00		
5	Painting Providing & applying White Plastic Emulsion paint of Asian Paints/ ICI Dulux/ Berger and Sporty Yellow-X104 shade of Royal Luxury Emulsion of Asian Paints in minimum 2 coats including scrapping, opening of existing cracks, filling up of "V" cracks with epoxy expandable putty to required depths, making good weak plastered/ unplastered surfaces with cement plaster wherever required. Item to include Plaster of Paris, primer, palti & making good existing surface to receive new paint including cleaning on completion of painting work etc. complete in all respects.	S.Ft.	0.00		
6	Entrance Door Providing and fixing Entrance Door (glazed) as per drawing no.11 in Silver Anodised aluminium door section (Jindal make) in top and bottom, glazed with 12 mm thick glass of approved make with etching and frosting. Item to include floor springs, lock, all necessary hardware of Stainless Steel finish as approved by the Project Consultant/ Bank complete in all respects.	S.Ft.	25.00		
7	Front Office Counter: Providing and fixing in position Front Office Counter 2'-6" wide as per drawing No.(1-A, 1-B, 1-C , 1-D & 15) comprising of the following complete in all respects:- i) Working top made with 25mm thick plywood finished with 1mm thick laminate. Outside edge of the working top shall be provided with 1½"x1" Teak Wood moulding finished with melamine polish. Inside edge will be provided with ½"x1" T.W. beading patti with melamine finish. ii) Vertical fascia (Apron) made with 18mm thick plywood finished with 1mm thick laminate with 1mm thick groove at the joint of laminates of two different shades.	RFT	14.00		



	<p>iii) Vertical drop (horizontal band) shall be provided on the fascia below the working top made with 18mm thick plywood finished with 1mm thick laminate with provision for concealed light, 1 mm thick groove shall be provided at the joint of two different shades of laminate.</p> <p>iv) Glazed partition above working top to be provided with 12mm thick clear glass cut to the standard shape fixed to partition as per fixing details and to boxing with concealed S. S. finished 'D' brackets as shown in the drawing. The exposed edges of the glass shall be finished in mirror polish.</p> <p>v) 3'-10" high Boxing (10"x10") made with 18 mm thick plywood finished with 1 mm thick laminate including providing and fixing 6 mm thick square frosted glass at a height 3'-2" above finished floor level.</p> <p>vi) 1'-9" high Boxing (5"x5") made with 12 mm thick plywood finished with 1 mm thick laminate.</p> <p>vii) vertical supports made with 18 mm thick plywood finished with white enamel paint.</p> <p>viii) Telescopic CPU Stand/ ready made Keyboard tray shall be provided of approved model and make.</p> <p>ix) Footrest made with T.W. member of size 4"x1 ½ " finished with french polish.</p> <p>x) Drawer units as per drawing shall be provided with multipurpose Godrej locks in</p> <p>Each drawer. Facia of drawer unit shall be finished with 1mm thick laminate and all other sides shall be finished with white enamel paint. The drawers will be provided with handles (Stainless Steel finish) and channels as per approval of the Project Consultant / Bank.</p> <p>xi) Boxing as per drawing made with 12mm thick plywood finished with Synthetic enamel paint shall be provided below the table top for electrical conduiting and at the bottom for the LAN cabling/Telephone wire conduiting.</p> <p>The item to include all necessary hardware and fittings in Stainless Steel finish, lipping to all edges and making provision only for electrical fitting behind the front. Vertical drop and also in the 10"x10" boxing as shown in the drawing. Necessary beadings with melamine polish for fixing the glass are to be provided.</p>				
8	<p>Cash Counter:</p> <p>Providing and fixing in position Cash Counter 2'-9" wide as per drawing No.(2-A, 2-B, 2-C, 2-D, 2-E, 2-F) comprising of the following :</p> <p>i) Working top made with 25mm thick plywood finished with 1mm thick laminate. Outside edge of the working top shall be provided with 1¼"x1" Teak Wood moulding finished with melamine polish. Inside edge will be provided with ½ "x1" T.W. beading patti with melamine polish.</p> <p>ii) Vertical facia (Apron) made with 18mm thick plywood finished with 1mm thick laminate with 1mm thick groove at the joint of laminates of two different shades.</p> <p>iii) Vertical drop (horizontal band) shall be provided on the fascia below the working top made with 18mm thick plywood finished with 1mm thick laminate with provision for concealed light, 1 mm thick groove shall be provided at the joint of two different shades of laminate.</p> <p>iv) Glazed partition of 1'-4" height above working top provided with 12mm thick toughened and frosted glass besides non-transparent film from inside fixed to partition as per fixing details and to boxing with concealed S. S. finished 'D' brackets as shown in the drawing. The exposed edges of the glass shall be finished in mirror polish.</p> <p>v) Transaction top shall be provided with 12mm thick toughened glass (partly glazed partly frosted) fixed horizontally with concealed Stainless Steel D bracket. Both exposed edges (inside and outside) shall be moulded and finished in mirror polish.</p> <p>vi) Glazed partition having height 1'.0" above the transaction top (in facia) shall be provided with 12 mm thick glass (clear) with cut out of 8"x 4" as per drawing. The edges of cut out and the top edge of glass are to be mirror polished and to be fixed to partition as per fixing details and to boxing with concealed S. S. finished 'D' brackets as shown in</p>	RFT	10.00		



	<p>vii) Glazed partition provided with 12mm thick glass (Clear) above the slit to be fixed to partition as per fixing details and to boxing with concealed S. S. finished 'D' brackets as shown in the drawing. . The exposed edges shall be finished in mirror polish.</p> <p>viii) 7'-7" high Boxing (10"x 10") made with 18mm thick plywood as per drawing with 1'-6" horizontal extension at the top including providing and fixing 6 mm thick square frosted glass at a height of 5"-11" above Finished Floor level.</p> <p>ix) 1'-9" high boxing (5"x 5") made with 12 mm thick plywood finished with 1 mm thick laminate are to be provided.</p> <p>x) Telescopic CPU Stand/ ready made Keyboard tray shall be provided of approved model and make.</p> <p>xi) Footrest made with T.W. member of size 4"x1 ½ " finished with french polish.</p> <p>xii) Drawer units as per drawing shall be provided and each drawer should have vertical partitions for keeping the currency notes and multipurpose Godrej locks. Facia of drawer unit shall be finished with 1mm thick laminate and all other sides shall be finished with white enamel paint. The drawers will be provided with handles (Stainless Steel finish) and channels as per approval of the Project Consultant / Bank.</p> <p>xi) Boxing as per drawing made with 12mm thick plywood finished with Synthetic enamel paint shall be provided below the table top for electrical conduiting and at the bottom for the LAN cabling/Telephone wire conduiting.</p> <p>The item to include all necessary hardware and fittings in Stainless Steel finish, lipping to all edges and making provision only for electrical fitting behind the Vertical drop and also in the 10"x10" boxing as shown in the drawing. Necessary beadings with matching melamine polish for fixing the glass are to be provided as per drawing/ as directed.</p>				
9	<p>Solid Full Height Partition</p> <p>Providing & fixing in position solid Full Height Partition in frame work including door in 2'x 2' grid (horizontally and vertically) comprising of 2"x 1½" T.W. Section with 6 mm thick plywood on both sides finished with 1 mm thick laminates of approved make and colour as shown in drawing no.17. Item to include 2" x 2" T.W. member for door frame. All exposed T.W. surfaces to be finished in melamine polish of matching laminate colour as directed including all necessary Stainless Steel finish fittings/ hardware, door closers, Godrej locks and wood preservative paint etc. as per list of approved material and as approved by the Project Consultant/ Bank complete in all respects.</p> <p>(Note: In case of false ceiling, the vertical T.W. members to be fixed with pucca ceiling but the area of partition payable will be below the false ceiling only).</p>	S.Ft.	360.00		
10	<p>Partly Glazed Full Height Partition</p> <p>Providing and fixing in position partly glazed Full Height Partition work as shown in the drawing nos. (3) & (4) including door as shown in the drawing No.(13) in frame work at 2' x 2 ' grid (horizontally and vertically) comprising of 2" x 1½" T.W. Section and / or as per frame work shown in the drawings with 6mm plywood on both sides finished with 1 mm thick laminates of approved shade and colour as shown in drawings. Item to include 8 mm thick glass with etching and frosting as per design and 2"x 2" T.W. member for door sides and glass sides and T.W. door frame to take 8 mm thick glass with etching and frosting. All exposed T.W. surfaces to be finished in melamine polish of matching laminate colour as directed including all necessary Stainless Steel finish fittings/ hardware, door closers, Godrej locks and wood preservative paint etc. as per list of approved material and as approved by the Project Consultant/ Bank complete in all respects.</p> <p>(Note: In case of false ceiling, the vertical T.W. members to be fixed with pucca ceiling but the area of partition payable will be below the false ceiling only).</p>	S.Ft.	190.00		

11	<p>Partly Glazed Partition for Cash Cabins</p> <p>Providing and fixing in position 7'-7" high partly glazed partition for Cash Cabins as per drawing nos. (2-A, 2-B, 2-C, 2-D & 2-E) including door drawing no.(12) in frame work at 2' x 2' grid (horizontally and vertically) comprising of 2" x 1½" T.W. Section and / or as per frame work shown in the drawings with 6mm plywood on both sides finished with 1 mm thick laminates of approved shade and colour as shown in drawings. Item to include 8 mm thick glass with etching and frosting as per design and 2"x 2" T.W. member for door sides and glass sides and T.W. door frame to take 8 mm thick glass with etching and frosting.</p> <p>The door will be provided with T.W. louvers finished in melamine polish of matching laminate colour. The doors are also to be provided with Godrej Night Latch. Two wooden trays are also to be provided as per drawing. Necessary cutouts are to provided in the glass and the edges of the glass cutouts are to be finished in mirror polish.</p> <p>All exposed T.W. surfaces to be finished in melamine polish of matching laminate colour as directed including all necessary Stainless Steel finish fittings/ hardware, door closers, Godrej locks and wood preservative paint etc. as per list of approved material and as approved by the Project Consultant/ Bank complete in all respects.</p>	S.Ft.	217.00		
12	<p>Partly Glazed Low Height Partition</p> <p>Providing and fixing in position partly glazed low height partition (21/2" thick) in frame work with T.W vertical members at 2' c/c and 3 horizontal members at equal distance comprising of 2"x 1½" T.W. Section with 6 mm plywood on both sides finished with 1 mm thick laminates of approved make and shade as shown in drawing no.(14) or (3). Item to include 12 mm thick glass (clear/frosted) to be fixed as shown in drawing. The exposed edges of the glass to be finished in mirror polish. T.W runner should be melamine polished in matching colour of laminate etc complete in all respects.</p>	S.Ft.	280.00		
13	<p>Manager's Table/Officer's Table</p> <p>Providing and fixing in position Manager's Table of size 5'-6"x 2'-6" as per drawing no.(6)/ Officer's Table of size 4'-6" x 2'-3" as per drawing no. (5) including Side Storage (Credenza) by using 25mm thick plywood for top and 18 mm thick plywood for all other horizontal and vertical members. Telescopic CPU Stand/ ready made Keyboard tray shall be provided of approved model and make. Footrest made with T.W. member of size 4"x 1 ½ " finished with french polish.</p> <p>Side Storage (Credenza) as per drawing shall be provided. Facia of Side Storage (Credenza) shall be finished with 1mm thick laminates as shown in the drawing and all other sides shall be finished with white enamel paint. The Side Storage (Credenza) shall be provided with handles (Stainless Steel finish) and channels as per approval of the Project Consultant / Bank.</p> <p>All exposed plywood surfaces to be finished with 1mm thk. laminate of approved make & shade, and all exposed edges of table top & ply verticals to have 1" x 1/4" T.W.lipping. All exposed T.W. sections to be melaminated and internal surfaces to have white enamel paint as directed. Item to include plywood boxing, all necessary hardware and fittings in Stainless Steel finish, lipping to all edges etc. complete in all respects.</p>	Each	1.00		
14	<p>Staff Table</p> <p>Providing and fixing in position Staff Table of size 5' 0"x 2' 5" as per drawing No.(5) by using 25mm thick plywood for top and 18 mm thick plywood for all other horizontal and vertical members. Telescopic CPU Stand/ ready made Keyboard tray shall be provided.</p> <p>Drawer units as per drawing shall be provided with multipurpose Godrej locks in each drawer. Facia of drawer unit shall be finished with 1mm thick laminate and all other sides shall be finished with white enamel paint. The drawers will be provided with handles (Stainless Steel finish) and channels as per approval of the Project Consultant / Bank.</p> <p>All exposed plywood surfaces to be finished with 1mm thk. laminate of approved make & shade, and all exposed edges of table top & ply verticals to have 1" x 1/4" T.W.lipping. All exposed T.W. sections to be melaminated and internal surfaces to have white enamel paint as directed. The item to include plywood boxing, all necessary hardware and fittings in Stainless Steel finish, lipping to all edges etc. complete in all respects.</p>	Each	1.00		

15	Full height Storage / Low Height Storage/ Back Storage(Credenza) Providing and fixing in position Full height Storage / Low Height Storage/ Back Storage(Credenza) as shown in Drg. No.(8), (9) & (10) respectively using Plywood of required thickness finished with 1mm thick laminates as shown in the drawing and all other sides shall be finished with white enamel paint as detailed therein. The Storage Units shall be provided with handles (Stainless Steel finish) as per approval of the Project Consultant / Bank. All exposed plywood surfaces to be finished with 1mm thk. laminate of approved make & shade and all exposed edges of plywood to have 1" x 1/4" T.W.lipping. All exposed T.W. sections to be melaminated in matching colour laminate and internal surfaces to have white enamel paint as directed. Item to include all necessary hardware and fittings in Stainless Steel finish, Godrej multi purpose locks including magnetic ball catcher etc., complete in all respects.	S.Ft.	82.00		
16	Planter -size 1'6"x1'6"x1'3" with 19mm board,1mm laminated & 12mm rubber wood all as per design	NOS	2.00		
17	PANELING WITH LAMINATE FINISH Providing & Fixing laminate finish paneling for walls, columns etc. made out of 2" X 1" C.P.T. Wood frame work at every 1'6" c/c (vertical/horizontal) both ways, covered with 10mm thick ply.All exposed surfaces of the paneling shall be finish with approved color 1.00 mm thk laminate complete as per detail drawing & instructions of Architect. (upto 8'0" height/False ceiling)	S.Ft.	215.00		
18	(SUGGESTION BOX) Providing and fixing one suggestion box, made with 12 mm ply as per standard design and specifications of the Bank, fully complete, with enamel painting, lock, lettering on top, etc.	Each	1.00		
19	Providing and fixing Cheque writing/slip rack projected/supported from wall 7'0" x1'-3" and a C.T. as per design with suggestion box,first aid box,suggestion box.	Each	1.00		
20	(CHECK DROP BOX) Providing and fixing one suggestion box, made with 12 mm ply as per standard design and specifications of the Bank, fully complete, with enamel painting, lock, lettering on top, etc.	Each	1.00		
21	Vertical blinds : Providing & fixing levelor 10mm vertical blinds having top rail 39mmX34mm hgh with wall thickness of 1.2mm having 25mm decorative insert. Control unit shall be of Derlin. Plastic runner shall be moulded from Derlin plastic with artification head rail & the top end of the louver fabric shall be polyster viscose/polyster yarn dyed in fast colour with or without protective coating on louvers with chemical for stain resistance and soil repetancy and shall have GI weight and steel/polymer ball chain for spacing. The top rail should be fixed on bracket of 14 SWG galvanized spring steel fixed firmly on walls by nylon plug and screw as per approved design and direction of the Architect. (Makes - Vista, Universal).	S.Ft.	0.00		
22	Dismantle & Removal of existing partition ,false ceiling, counters etc in Branch Room.debris from site, carrying and disposal of malba to dumpyard. as per bank/branch incharge direction. (Branch)	LS	1.00		
23	Panel box covering : Shall be made up of 19mm th BWP boarer free ISI marked -Fire resistant ply on all the sides. shutter shall be of 19mm th block board of BWPgrade ISI marked-Fire resistant (Minimum 2 hr.) and shall have holes 1/2" dia (25nos.) for ventilation and have glass piece (9"x9") for meter reading and shall be finished with 1.00mm laminate of approved shade on all exposed sides and inside finished with 0.8 mm thick laminated. The rate is inclusive of all locks of Godrej or equivalent make, SS tower bolts, SS handles, heavy duty SS hinges etc.all hardware complete. Prior confirmation shall be obtained from the officer in charge for all the hardware, locks and fixture etc, complete. (Note :- Box should not touch the ground)	SQ.FT.	0		
	TOTAL				
	G.S.T(Extra as applicable)				
	Notes:-				
	Contractor to Note that:-				
a)	Footrests to be provided (laminated) with each table / counter without any extra charges, @ 1 per person.				
b)	Extra members, wherever required for stability / otherwise, to be provided with the required finish without ant extra charges.				

